



MORIN BUILDING
8570 EXECUTIVE PARK AVENUE
FAIRFAX, VIRGINIA 22116-0815

Wednesday, October 2, 2024

To: All Prospective Bidders

Issued by: David Webb C.P.M., Procurement Program Supervisor

Subject: Addendum 3 to IFB 24-214 –Reston and Popes Head PS Electrical Upgrades

The purpose of this addendum is to make revisions to the IFB.

I. Additions, Deletions, Corrections, and Revisions to the IFB

Reference Drawing (ex. A-101) or Spec Section (ex. 00400)	Comment:
Sheet 5 of 34, Drawing C-3, General Note 5	CHANGE: CONTRACTOR SHALL USE HAND TOOLS ONLY (NO MECHANICAL EQUIPMENT) FOR EXCAVATION WITHIN THE TEMPORARY LIMIT OF DISTURBANCE. WITH: CONTRACTOR SHALL USE HAND TOOLS ONLY (NO MECHANICAL EQUIPMENT) FOR EXCAVATION WITHIN 5-FEET OF OWNER’S EXISTING WATER MAIN.

II. Questions. Fairfax Water official responses are provided in *Italics*:

#	<u>Question:</u>	<u>Answer:</u>
1	Drawing C-3, General Note 5: This note states to use only hand tools (no mechanical equipment) for excavation. Is there a reason for this requirement? Concrete demolition will require equipment such as jack hammers, saws and hammers. Is this also restricted?	<p><i>General Note 5 is intended to apply at the crossing of the OWNER’s existing water main and the proposed concrete encased duct bank within the temporary limits of disturbance.</i></p> <p><i>See amendment to Drawing C-3 in Section I, above.</i></p>
2	Please clarify the requirements for field painting. Are any undisturbed existing surfaces required to be painted?	<p><i>Reston Pump Station - For painting requirements, please refer to Section 16131, Part 3.2. D (p. 527 of 634) – ‘Restore walls, floor, and roof to original condition such as watertight, fire rating, smooth and/or painted finish after duct raceway penetration.</i></p> <p><i>Popes Head Pump Station – See Table 09900-B for Painting Schedule.</i></p>
3	The Specifications state that Process Control is by the Owner. Please clarify Contractor’s responsibility for new instrument devices, if any.	<p><i>Reston Pump Station - For Contractor’s process control responsibilities, please refer to Section 13610, Part 1.2. Generally, the Contractor is responsible for procurement and installation of any instruments. The Contractor will wire the instrument and will perform point to point testing and instrument calibration. Once complete, the Owner will configure the I/O from the instrument in the PLC and HMI.</i></p>
4.	Would it be possible to arrange another visit to the Reston Pump Station	<i>Yes. An additional site visit has been arranged only for the Reston Pump Station at 9:00 AM on Tuesday, October 8, 2024,</i>

Acknowledge your receipt of, and compliance with, this Addendum by either signing the attached acknowledgement, or referencing its receipt and your compliance, in your bid.

END OF ADDENDUM NO. 3

ACKNOWLEDGEMENT OF RECEIPT OF ADDENDUM # 3

I certify that the information contained in the proposal submitted on behalf of the below named firm incorporates any and all changes to the original specification. I further certify by my signature below, that I am fully authorized to acknowledge receipt of the above addendum and also bind the below named firm to the terms, conditions and specifications of the IFB and any changes thereto made by this addendum.

ACKNOWLEDGED BY:

FOR: _____

Company Name

Date

Signature of Authorized Agent

Printed/typed name

Title